

# **Establishing a Cost Basis for Converting the High Flux Isotope Reactor from High Enriched to Low Enriched Uranium Fuel**

**January 31, 2010**

**Prepared by**

**Tracey Guida  
R. T. Primm, III**



## DOCUMENT AVAILABILITY

Reports produced after January 1, 1996, are generally available free via the U.S. Department of Energy (DOE) Information Bridge.

**Web site** <http://www.osti.gov/bridge>

Reports produced before January 1, 1996, may be purchased by members of the public from the following source.

National Technical Information Service  
5285 Port Royal Road  
Springfield, VA 22161

**Telephone** 703-605-6000 (1-800-553-6847)

**TDD** 703-487-4639

**Fax** 703-605-6900

**E-mail** [info@ntis.gov](mailto:info@ntis.gov)

**Web site** <http://www.ntis.gov/support/ordernowabout.htm>

Reports are available to DOE employees, DOE contractors, Energy Technology Data Exchange (ETDE) representatives, and International Nuclear Information System (INIS) representatives from the following source.

Office of Scientific and Technical Information  
P.O. Box 62  
Oak Ridge, TN 37831

**Telephone** 865-576-8401

**Fax** 865-576-5728

**E-mail** [reports@osti.gov](mailto:reports@osti.gov)

**Web site** <http://www.osti.gov/contact.html>

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Research Reactors Division

ESTABLISHING A COST BASIS FOR CONVERTING THE HIGH FLUX ISOTOPE  
REACTOR FROM HIGH ENRICHED TO LOW ENRICHED URANIUM FUEL

Tracey Guida\*  
R. T. Primm, III

\*University of Pittsburgh

Date Published: January 2010

Prepared by  
OAK RIDGE NATIONAL LABORATORY  
Oak Ridge, Tennessee 37831-6283  
managed by  
UT-BATTELLE, LLC  
for the  
U.S. DEPARTMENT OF ENERGY  
under contract DE-AC05-00OR22725



## CONTENTS

LIST OF FIGURES .....	v
LIST OF TABLES .....	vii
ACKNOWLEDGEMENT .....	ix
ACRONYMS AND ABBREVIATIONS .....	xi
ABSTRACT .....	xiii
1. INTRODUCTION .....	1
1.1 Description of HFIR .....	1
1.2 Policy Assumptions .....	2
1.3 Methodology .....	4
2. COMPONENTS OF THE POST-FABRICATION HFIR FUEL CYCLE .....	7
2.1 Input Required from Organizations Outside ORNL .....	7
2.2 Quality Assurance Monitoring/Approval by HFIR Staff .....	7
2.3 LEU Fuel Design Studies .....	7
2.4 Fresh Fuel Shipping Container .....	8
2.5 Fresh Fuel Storage .....	8
2.6 Operations Inside the HFIR Building .....	8
2.7 Operations with Spent Fuel Outside the Reactor .....	11
3. SUMMARY AND CONCLUSIONS .....	15
4. REFERENCES .....	17
Appendix A. RISKS AND OPPORTUNITIES .....	19



## LIST OF FIGURES

	<b>Page</b>
1. HFIR fuel elements .....	1
3.1 Conversion project annual expense .....	14
3.2 HFIR LEU conversion cost by topic .....	15





## LIST OF TABLES

	<b>Page</b>
2.1	Input required for organizations outside ORNL .....9
2.2	Quality Assurance, Design, and Fresh Fuel Shipping Tasks .....10
2.3	Operations conducted inside the HFIR building.....12
2.4	Spent fuel operations outside reactor .....13
3.1	HFIR LEU conversion cost.....15



## ACKNOWLEDGMENTS

The authors would like to acknowledge that the support for this project was provided by the Global Threat Reduction Initiative, Reduced Enrichment for Research and Test Reactors Program, National Nuclear Security Administration, U.S. Department of Energy. The first author, Tracey Guida, was a participant in the Pre-Service Teacher Training Fellowship Program at Oak Ridge National Laboratory during the time these studies were conducted. Appendix A was prepared by D. G. Renfro, Research Reactors Division (RRD), Oak Ridge National Laboratory (ORNL). Review of the manuscript by Kevin A. Smith and the careful formatting of the document by Mary Wells, both of RRD, ORNL, are very much appreciated and acknowledged.



## ACRONYMS AND ABBREVIATIONS

ATR	Advanced Test Reactor
DOE	U.S. Department of Energy
HEU	high enriched uranium
HFIR	High Flux Isotope Reactor
IFE	inner fuel element
INL	Idaho National Laboratory
ISM	Integrated Safety Management
LEU	low enriched uranium
NNSA/DOE	National Nuclear Security Administration/Department of Energy
OFE	outer fuel element
ORNL	Oak Ridge National Laboratory
RERTR	Reduced Enrichment for Research and Test Reactors Program
SNF	Spent Nuclear Fuel
SRS	Savannah River Site
SST	safe, secure transport



## ABSTRACT

Under the auspices of the Global Threat Reduction Initiative – Reduced Enrichment for Research and Test Reactors Program, the National Nuclear Security Administration /Department of Energy (NNSA/DOE) has, as a goal, to convert research reactors worldwide from weapons grade to non-weapons grade uranium. The High Flux Isotope Reactor (HFIR) at Oak Ridge National Laboratory (ORNL) is one of the candidates for conversion of fuel from high enriched uranium (HEU) to low enriched uranium (LEU). A preliminary plan, including tasks, costs, and schedules for conversion of HFIR fuel was developed to provide initial input to the multi-reactor conversion program integrated plan. Using Microsoft Project, a detailed outline of the conversion program was established and consists of LEU fuel design activities, a fresh fuel shipping cask, improvements to the HFIR reactor building, and spent fuel operations. Current-value costs total \$76 million dollars, include over 100 subtasks, and will take over 10 years to complete. The model and schedule follow the path of the fuel from receipt from fuel fabricator to delivery to spent fuel storage and illustrates the duration, start, and completion dates of each subtask to be completed. Assumptions that form the basis of the cost estimate have significant impact on cost and schedule. This preliminary plan is subject to revision based on feedback from the multi-reactor conversion program manager and other emerging developments.





## 1. INTRODUCTION

An engineering design study for a fuel that would enable the conversion of the High Flux Isotope Reactor (HFIR) from high enriched uranium (HEU) to low enriched uranium (LEU) is ongoing as part of an effort sponsored by the U.S. Department of Energy's (DOE) National Nuclear Security Administration through the Global Threat Reduction Initiative/ Reduced Enrichment for Research and Test Reactors Program (RERTR). The conversion of the reactor implies the creation of a new fuel cycle both because the form of the LEU fuel is different from the current HEU fuel – a metal alloy rather than a blend of ceramic and metal powders – and because achieving the goal of a proliferation resistant fuel cycle makes obsolete the transportation and storage processes that have been in use for over 40 years. A study was conducted of the impact of fuel conversion on all parts of the fuel cycle that follow fabrication of HFIR fuel elements. The study was performed to provide input to a larger, five-reactor integrated conversion program schedule being developed at the Idaho National Laboratory.


### 1.1 DESCRIPTION OF HFIR

The HFIR is an 85 MW, very high flux, pressurized light-water-cooled and moderated, flux-trap type reactor, which is operated at the Oak Ridge National Laboratory (ORNL). The primary mission of HFIR is to support neutron scattering experiments. Other missions include isotope production, materials irradiation research, and neutron activation analyses. The reactor core consists of a series of concentric annular regions: a central flux trap containing vertical experimental targets surrounded by two fuel elements separated by a thin water region, a region containing two control plates, a beryllium reflector, and a water region to the edge of the pressure vessel, which is located in a pool of water. Details of the reactor configuration and operation can be found elsewhere.<sup>1,2</sup>

The two fuel elements in HFIR are identified as inner fuel element (IFE) and outer fuel element (OFE). They are composed of numerous, involute-shaped fuel plates 1.27 mm-thick, as illustrated in Fig. 1.(a). The plates are separated by a water-filled cooling channel 1.27 mm-thick, and are held together by two cylindrical aluminum side walls. The fuel plates have a sandwich-type design, with a fuel region enclosed in an aluminum-based clad, as illustrated in Fig. 1.(b). The current, HEU, fuel meat inside the fuel region contains a mixture of aluminum powder and uranium oxide ( $U_3O_8$ ) with 93.1 wt %  $^{235}U$  enrichment and is characterized by variable thickness along the width of the fuel plate (radial grading) and a uniform thickness along the length of the fuel plate for a given radius (no axial grading).



a) inner and outer fuel elements



(b) fuel plate profile

**Fig. 1. HFIR fuel elements.**

LEU fuel for HFIR will have the same geometry and dimensions as shown in Fig. 1 but the fuel “meat” region, designated as “fuel” in Fig. 1b, will be an alloy of uranium and molybdenum; the uranium having an enrichment of 19.75%. The fuel will have a graded thickness as is shown in Fig. 1b but the profile will be different from the current fuel. The current design for the LEU fuel is for the fuel to have an axial variation in fuel thickness (axial grading) along the lowermost 3 cm of the fuel. Design studies of the LEU fuel are reported in Refs. 3-5.

## 1.2 POLICY ASSUMPTIONS

Questions of cost and schedule for HFIR fuel conversion were first addressed in Ref. 3. A result of those studies was the observation that obtaining even order-of-magnitude cost estimates required establishing certain assumptions some of which had not yet been considered, much less approved, by program management. Likewise for this study, various “ground rules” were established at the start of the study. These ground rules are elaborated below along with any corollaries that derive from the assumptions.

- 1) *The Department of Energy – Office of Science endorses the conversion of HFIR from HEU to LEU fuel.* On September 29, 2009, a letter was sent from Dr. Kelly Beierschmitt, Oak Ridge National Laboratory, to Dr. Parrish Staples, National Nuclear Security Administration, Department of Energy in which Dr. Beierschmitt stated, “it is theoretically feasible to convert the reactor to the use of monolithic U/Mo LEU fuel”. While it is the responsibility of NNSA to develop the LEU fuel and fund this development, HFIR staff, funded by Office of Science to operate the HFIR, will be needed to perform many of the analyses/tasks described subsequently in the schedule. The HFIR facility, itself, will be needed for the conduction of reactor physics tests for LEU fuel. It is assumed that Office of Science will allow these resources to be assigned to NNSA to conduct the tasks identified in the schedule.
- 2) *Organizations outside of ORNL complete identified tasks as scheduled.* The LEU conversion program is divided among many organizations including Idaho National Laboratory, Los Alamos National Laboratory, Argonne National Laboratory, the Y-12 National Security Complex, Babcock and Wilcox Nuclear Operations Group, and Oregon State University. It is the responsibility of ORNL to identify input needed from these organizations as part of the integrated conversion program schedule. These items are noted in the schedule presented in this document. It is the responsibility of the conversion program to fund the requested items, ensure the quality of the items, and deliver them to ORNL according to the conversion program integrated schedule.
- 3) *All LEU conversion operations at HFIR will be conducted in compliance with the ORNL Research Reactors Division engineering configuration management process and the elements of DOE-STD-1189 (Ref. 6).* DOE-STD-1189 addresses integration of safety into the design process. These processes were considered in the HFIR schedule.
- 4) *With the creation of separate interim and commercial fuel fabrication tasks, if HFIR fuel is fabricated as a part of the interim fuel fabrication task, NNSA will fund the first HFIR reactor core from each task, that is, the first from interim and the first from commercial.* Since the beginning of the LEU conversion program, NNSA has agreed to fund the initial LEU core loaded to HFIR. At the inception of the LEU conversion program, it was not envisioned that there would be a separate, interim fuel fabrication task. Since interim and commercial fuel fabricators may employ different processes, likely will employ different groups of people, and certainly will be at different physical locations, it is the responsibility of NNSA to fund the initial HFIR core from each fabrication task.

- 5) *HFIR LEU fuel will be stored at the Y-12 site.* Since the startup of HFIR, the fresh fuel, being HEU, has been stored at the Y-12 plant. Currently 24 cores – about 3 years of inventory at the current consumption rate – are stored at Y-12. Mr. Morris E. Hassler, Director of Strategic Development / Science, Technology, and Partnerships / Y-12 provided the following information by electronic mail correspondence, “Y-12 will continue to store HFIR fresh fuel in the future. As the fuel is converted from HEU to LEU, Y-12 will then store the HFIR fresh fuel in lower category storage areas instead of high security storage areas as we do now. The Y-12 Master Plan (Y/MOD-0150) documents this continued storage of Category III/IV materials. The LEU materials will be stored in the current warehouse after the HEU material is moved out. Also, I reviewed the latest Y-12 SWEIS (DOE/EIS-0387) and it mentions specifically continuing to support research reactors in supplying fuels including LEU.”
- 6) *After the initiation of fueling of the other U.S.HEU-fueled reactors with LEU, NNSA will compensate HFIR for any increase in HEU fuel fabrication cost that is attributable to a reduction in demand for HEU fuel fabrication services.* HFIR fuel operations are not independent of the other four, high performance reactors. The reduction in HEU use as reactors are converted will lead to a greater portion of the fuel fabrication burden (overhead) being assigned to HFIR. Compensation for this increase is consistent with NNSA statements that operations at reactors will not be significantly affected by fuel conversion. HFIR operations must be insured against added fuel costs due to being the last reactor to convert.
- 7) *Savannah River Site will be the disposal point for spent LEU fuel and therefore the end point for any ORNL responsibility related to HFIR fuel.*

Through the National Environmental Policy Act, a decision was made in 1995 to consolidate DOE-owned SNF [spent nuclear fuel] at existing DOE sites that have the skills, facilities, and technologies to best handle the fuel. Based on the decisions from the associated environmental impact statement, DOE will temporarily store its SNF at the Hanford Site in Washington, the Idaho National Laboratory (INL) in Idaho, and the Savannah River Site (SRS) in South Carolina until a repository is completed. The Hanford Site will retain most of its current inventory of SNF. The remaining DOE SNF will be consolidated at either the INL or SRS, depending on the type of fuel. . . . SRS provides for the safe receipt and interim storage of SNF assemblies including SNF from domestic and foreign test and research reactors. Only L-Basin still contains and receives SNF. The basins have concrete walls 3 feet thick and hold 3.5 million gallons of water with pool depths of 17 to 30 feet to provide cooling and shielding to protect workers from radiation. The SNF stored and received at L-Basin is either planned to be transferred to H-Area facilities for processing and disposition or to INL for consolidation and to prepare and package into a “road ready” condition. (Ref. 7)

HFIR will fabricate whatever tools are necessary to unload LEU fuel at Savannah River site and will be responsible for any required engineering analyses up to the point at which Savannah River Site takes custody of the LEU fuel.

- 8) *Since the overall cost associated with conversion to LEU fuel should not increase the annual operating expenditure for the owner/operator, NNSA will fund any increase in annual operating costs due to LEU for the lifetime of the reactor.* Frequently, when changing an industrial process, there is more than one path to achieving the desired outcome. Choices result in a trade-off between capital investment and labor cost; increasing one lowers the other. In these studies, when options were available, the choice was made to maintain (or minimize the increase in)

operating cost at the expense of potentially higher capital cost (investment). The LEU conversion program will support the choice that minimizes annual operating (labor) cost to HFIR. Staff at ORNL have estimated that the annual production cost of LEU fuel will be at least twice the annual cost of HEU fuel (Ref. 8) even continuing to assume that the cost of the LEU itself is not included (Ref. 3). Therefore, because the current, HEU fuel cost is approximately 15% of the total operating budget for HFIR, it has been assumed that NNSA will provide a 10%-of-operating-cost subsidy to HFIR for every year that the HFIR operates once conversion of HFIR to LEU fuel is achieved. The financial implications of this policy assumption are significant - a potential cost of over \$200 million – and, in fact, far exceed the sum of the costs of all other items in the HFIR conversion schedule. Furthermore, the actual cost of the LEU fuel will not be known until a commercial process attains greater definition/development than that described in Ref. 8. It is possible that LEU fuel cost could be the same or less than HEU fuel cost once a fabrication facility is constructed, especially if the RERTR program adheres to the philosophy of minimizing operating cost even at the expense of increased capital cost. As a consequence, this estimated, annual subsidy is *not* included in the schedule and costs presented subsequently as the authors felt it would obscure/overwhelm other, important concerns. This policy issue, though, should be acknowledged and addressed by the appropriate parties funding HFIR studies and operations.

### 1.3 METHODOLOGY

Determination of the components of the conversion schedule, the duration of the tasks, and the estimated cost were made using the same methodology as described in Ref. 3. The schedule was prepared using the Delphi technique and is based on a “success-driven” assumption, that is, the assumption is made that no unforeseen problems occur during the lifetime of the project.

Managers in the ORNL Research Reactors Division responsible for operations, safety, fabrication, and environmental impact were consulted for cost and scheduling estimates for changes to the HFIR site to accommodate an LEU fuel cycle. The result of these discussions was a preliminary cost estimate of the required capital improvements, safety analysis updates, changes to Technical Safety Requirements, procedural modifications, and required training to support the implementation of core conversion.

The assessment was limited to operations at the HFIR site (7900 area of ORNL) because the RERTR program has funded other organizations to develop fuel production capabilities and fuel plate and fuel element fabrication capabilities. Consequently, these fuel production costs were excluded from this study. The cost of 19.75% enriched uranium was also not considered. Currently the HFIR annual budget includes payment for the processing of HEU into  $U_3O_8$  but not for the HEU itself. Possible sources of LEU include down-blending HEU or the purchase of the material from an enrichment facility. Either would incur costs that are not a part of the HEU fuel cycle. Likewise, an assessment of the acceptability of uranium-molybdenum for long-term storage of spent fuel was not performed because that operation will not be at the ORNL site. (Ref. 3, p. 19)

The schedule includes capital improvements required to HFIR to run the reactor with the LEU fuel at 100 MW to recover the flux lost to the beam tubes due to converting from HEU to LEU.

The HFIR schedule development process began by tracing the path of the fuel elements from the time they left the fuel fabrication facility until they were delivered to the Savannah River Site. Current costs for these operations with HEU fuel are known. Consequently the staff focused on differences between the HEU and LEU fuel cycles and then estimated the time and cost to resolve or accommodate these differences. The completion date for conversion was constrained to be the loading of the first LEU core to HFIR by the end of fiscal year 2016 (September 30, 2016) to meet conversion program integrated schedule expectations. The schedule was developed by working backwards in time from that date. Dates

of completion for activities by others have been assumed. A secondary consideration was to levelize the annual expenditures as much as possible (similar level of funding year-to-year).

Per request of program management, Microsoft Project software was used to prepare the schedule. Upon completion of the study documented here, the draft Project file was forwarded to program management in September 2009 for integration into a multi-facility schedule. Subsequent to providing the requested schedule to program management, two policy decisions were made that resulted in deletions from the original schedule – deletion of a fresh fuel storage facility at the HFIR site and deletion of a parity HEU fuel experiment. Hence, tables, charts, and graphs contained in this report are a subset of those contained in the version of the Project file that was previously supplied to program management. No additions and no other schedule adjustments were made to the file that had been sent to program management. A revised file will be provided to reflect these deletions. Some comments regarding risks and opportunities associated with the schedule that were requested by program management are provided in Appendix A. Based on feedback from the conversion program manager, this HFIR conversion plan will be updated to reflect integration with the overall conversion program plan.



## **2. COMPONENTS OF THE POST-FABRICATION HFIR FUEL CYCLE**

The HFIR schedule can be subdivided according to fuel operations, i.e. transportation, irradiation, spent fuel storage, spent fuel transportation, etc. Each of these subdivisions is presented separately.

### **2.1 INPUT REQUIRED FROM ORGANIZATIONS OUTSIDE ORNL**

The HFIR conversion schedule is a portion of a large effort to prepare an integrated conversion schedule for all U.S. high performance reactors. To enable integration, those areas in which input is needed from organizations outside ORNL before work can begin at HFIR have been collected into a single schedule category. With a few notable exceptions, there are no ORNL costs associated with the provision of these data. Yet the data must be provided on a timely basis if ORNL is to meet the schedule documented here. Table 2.1 contains a list of data/information needs.

Entries 5-16 of Table 2.1 correspond to the policy assumptions enumerated in Section 1.2. These entries are the only ones for which costs accrue at ORNL. The principal cost, \$8.4 million, corresponds to the estimated increase in HFIR HEU fuel cost during the time period before HFIR conversion and due to conversion of the other high performance reactors. The figure is derived from the fact that approximately 25% of the annual cost of production of U.S. HEU research reactor fuel is for reactors other than HFIR and the Advanced Test Reactor (ATR). If that production cost is borne by HFIR for six years, an incremental cost of \$8.4 million is found.

LEU fuel qualification is the responsibility of INL. Hydraulic flow test data will be measured in experiments performed at Oregon State University under the direction of INL. These data will be one of components of the safety basis for LEU fuel in HFIR and are needed before safety-related analyses are initiated.

Similar to fuel qualification, fuel fabrication data are needed in order to define manufacturing tolerances for fuel parameters. Both design basis tolerances (manufacturing specifications) and the accuracy and precision of the devices to be used to confirm design dimensions and fuel characteristics are needed. These data are input to safety-related analyses.

### **2.2 QUALITY ASSURANCE MONITORING/APPROVAL BY HFIR STAFF**

Entries 55-64 of Table 2.2 are “placeholders”. HFIR quality assurance staff are actively involved in all phases of the current, HEU fuel cycle. Powder production, shipping and transportation, and fuel fabrication operations are all monitored and reviewed by HFIR staff. Safe operation of the reactor – the responsibility of the HFIR staff – requires that fuel be manufactured to exacting standards. This same relationship must be established for a new, LEU fuel cycle. As has been noted earlier in this report, insufficient information on the reference production process exists (Ref. 8). Lack of data inhibits accurate estimation of cost and schedule. Due to the relatively short time to conversion, HFIR staff should be made aware of the fabrication processes as they are being developed. Estimated costs generally reflect 1 to 2 person-months of effort per fiscal year per segment of the fabrication process and allow for the fact that fuel fabrication operations will be geographically distant from Oak Ridge.

### **2.3 LEU FUEL DESIGN STUDIES**

Entries 66-86 of Table 2.2 are the continuation of studies initiated in 2005 at ORNL; initial studies documented in Ref. 3-5. The goals of these future studies are to document the current LEU HFIR fuel design, develop engineering drawings, and forward these data to fuel qualification and fuel fabrication tasks. In addition, thermal hydraulics studies will be conducted with the aim of developing and certifying advanced, finite-element-based analysis techniques. Studies to date indicate that by using these modern

analysis techniques, unnecessary conservatism in the current LEU HFIR fuel design could be eliminated and therefore the fabrication processes made to be simpler and cheaper.

For the current, HEU fuel cycle, the fuel manufacturing specification was developed by ORNL staff and then supplied to the fabricator as a part of the contracting process for procuring reactor fuel. Revisions to the fuel specification are the contractual responsibility of the HFIR staff. Contractually, the fuel specification for LEU fuel will be required to be approved by the staff of the contractor for Oak Ridge National Laboratory. This contractual requirement, coupled with the technical expertise of the HFIR staff (Ref. 8), are the bases for the table entries related to materials and fabrication.

## **2.4 FRESH FUEL SHIPPING CONTAINER**

The HFIR LEU core geometry will be unchanged from the current HEU design. Consequently the LEU core will fit into the current shipping container. However, the weight of an LEU core will be approximately 30% greater than the current HEU core. Furthermore, due to the changes in both the quantity and enrichment of uranium, the container must be relicensed. Relicensing includes, among other things, structural and criticality safety analyses. Currently, HEU fuel elements are transported by safe, secure transport (SST). With the reduction in enrichment, commercial transport may be utilized. There is some possibility that the current fresh fuel shipping containers, even when reanalyzed for LEU fuel, would not be acceptable to licensing authorities. Three federal agencies, Department of Energy, Department of Transportation, and the Nuclear Regulatory Commission, will have to certify the new container for LEU fuel. These analyses and reviews are reflected in entries 88-103 of Table 2.2.

## **2.5 FRESH FUEL STORAGE**

HFIR is refueled 7-8 times a year. At each refueling, both inner and outer elements are replaced. Since the HFIR fuel cycle is short (~25 days) and since the production time for a HFIR fuel element is approximately 2 years, the goal for the inventory of fresh HFIR elements has been set at a level to meet four years of consumption (30-32 cores at the current rate of consumption). At present, the Department of Energy has authorized the storage of 3 fresh cores at the HFIR site. Usually there is only one fresh core on site at HFIR and that occurs on a just-in-time basis. Delivery of the fresh core is usually scheduled just before expected cycle shutdown and one goal of operations at HFIR is to have the fresh fuel located outside the reactor vessel for the minimum amount of time. Consequently the balance of the inventory of HFIR elements (currently 24 cores) is stored at the Y-12 plant.

LEU fuel will be stored at Y-12 in lower category storage areas instead of high security storage areas currently used for HEU. The Y-12 Master Plan (Y/MOD-0150) documents this continued storage of Category III/IV materials. No significant changes in cost are expected with LEU HFIR assemblies. Fresh fuel storage has no impact on the HFIR conversion schedule.

## **2.6 OPERATIONS INSIDE THE HFIR BUILDING**

The building containing the High Flux Isotope Reactor is designated as 7900 and includes fresh fuel receipt areas, spent fuel storage arrays, various balance-of-plant systems, and research areas for experimenters. Since LEU elements will be approximately 30% heavier than the current HEU elements and since various fuel handling tools are certified only for operation with current elements, expert opinion is that new fuel handling tools must be designed, fabricated and certified for use with LEU elements. Structural analyses must be performed for both fresh and spent fuel operations.



Table 2.1 Input required from organizations outside ORNL

ID	Task Name	Cost	Duration	Start	Finish
3	<b>Input required from organizations outside UT-Battelle/ORNL</b>	<b>\$8,460,000.00</b>	<b>89.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 8/2/16</b>
4	<b>Policy decisions</b>	<b>\$8,460,000.00</b>	<b>89.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 8/2/16</b>
5	<b>NNSA and DOE-Office of Science</b>	<b>\$8,450,000.00</b>	<b>89.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 8/2/16</b>
6	HFIR staff prepare presentation to Office of Science	\$20,000.00	1 mon	Thu 10/1/09	Wed 10/28/09
7	Office of Science/NNSA workshop to discuss HFIR status within GTRI	\$5,000.00	0.5 mons	Mon 11/2/09	Fri 11/13/09
8	If within GTRI scope, specification of degree of compliance with DOE-STD-1189	\$5,000.00	0.5 mons	Mon 11/16/09	Fri 11/27/09
9	Memorandum of Understanding (MOU) issued between Office of Science and NNSA regarding HFIR status	\$5,000.00	1 mon	Mon 11/30/09	Fri 12/25/09
10	Memorandum of Understanding that NNSA covers costs through first HFIR core from FFC and first core from interi	\$5,000.00	0.5 mons	Mon 12/28/09	Fri 1/8/10
11	Memorandum of Understanding that NNSA provides for HFIR fresh fuel storage and location	\$5,000.00	0.5 mons	Mon 1/11/10	Fri 1/22/10
12	MOU between SC and NNSA that NNSA fund 10% of HFIR annual budget for remaining HFIR life	\$5,000.00	0.5 mons	Mon 1/25/10	Fri 2/5/10
13	Compensation to HFIR for increased HEU production cost due to conversion of other research reactors	\$8,400,000.00	24 mons	Wed 10/1/14	Tue 8/2/16
14	<b>NNSA, DOE-Office of Science, and Savannah River Site (SRS)</b>	<b>\$10,000.00</b>	<b>1 mon</b>	<b>Mon 2/1/10</b>	<b>Fri 2/26/10</b>
15	Inform SRS that (Zr-encased, LEU/Mo fuel) clad with Al will be delivered for disposition per DOE EIS	\$5,000.00	0.5 mons	Mon 2/1/10	Fri 2/12/10
16	Memorandum of Understanding between SRS and Office of Science on acceptability of LEU fuel	\$5,000.00	0.5 mons	Mon 2/15/10	Fri 2/26/10
17	<b>Fuel Qualification Data/Analyses/Reports</b>	<b>\$0.00</b>	<b>38.1 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 8/31/12</b>
18	<b>INL (ATR irradiations)</b>	<b>\$0.00</b>	<b>38.1 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 8/31/12</b>
19	Distribute program plan for remainder of U/Mo irradiation experiments	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
20	Summary/topical report of U/Mo fuel irradiations performed by RERTR	\$0.00	0.2 mons	Mon 3/1/10	Thu 3/4/10
21	Incorporation of RERTR U/Mo data with other U/Mo data to complete U/Mo Handbook	\$0.00	0.2 mons	Thu 4/1/10	Tue 4/6/10
22	<b>Single driver element in ATR</b>	<b>\$0.00</b>	<b>25.05 mons</b>	<b>Thu 10/1/09</b>	<b>Thu 9/1/11</b>
23	ORNL attendance at discussions/meetings on approval process for loading LEU fuel to ATR	\$0.00	12 mons	Thu 10/1/09	Wed 9/1/10
24	Summary/topical report of LEU assembly irradiation in ATR	\$0.00	12 mons	Fri 10/1/10	Thu 9/1/11
25	<b>Multi-element test in one lobe of ATR</b>	<b>\$0.00</b>	<b>12 mons</b>	<b>Mon 10/3/11</b>	<b>Fri 8/31/12</b>
26	ORNL attendance at discussions/meetings on approval process for loading LEU fuel to ATR	\$0.00	12 mons	Mon 10/3/11	Fri 8/31/12
27	Summary/topical report of LEU assembly irradiation in ATR	\$0.00	12 mons	Mon 10/3/11	Fri 8/31/12
28	<b>Oregon State University (Flow Test Loop)</b>	<b>\$0.00</b>	<b>16.35 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 12/31/10</b>
29	OSU to form advisory committee that includes HFIR representative	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
30	OSU to consider two separate test loops: one for MIT/MURR/NIST and second for ATR/HFIR	\$0.00	0.2 mons	Tue 12/1/09	Fri 12/4/09
31	OSU/HFIR to develop two surrogate HFIR assemblies: inner element and outer element	\$0.00	12 mons	Mon 2/1/10	Fri 12/31/10
32	OSU/HFIR to mutually decide on scope of test matrix	\$0.00	0.2 mons	Thu 4/1/10	Tue 4/6/10
33	Receive data from structural analysis tests	\$0.00	0.2 mons	Fri 10/1/10	Wed 10/6/10
34	HFIR/OSU determine if heated flow test data are needed/if so modify facility/send data to HFIR	\$0.00	0.2 mons	Fri 10/1/10	Wed 10/6/10
35	<b>Fuel Fabrication Data/Analyses/Reports</b>	<b>\$0.00</b>	<b>6.7 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 4/6/10</b>
36	<b>Y-12 (HEU downblend and alloying with Mo)</b>	<b>\$0.00</b>	<b>0.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 10/6/09</b>
37	Identification of contact for quality assurance information/requirements exchange	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
38	Provide specifications for HEU down-blending and alloying fabrication steps	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
39	Supply samples for fuel qualification tests	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
40	Supply estimate of expected cost per plate of operations	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
41	<b>LANL (Interim fuel fabrication)</b>	<b>\$0.00</b>	<b>4.6 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 2/5/10</b>
42	Identification of contact for quality assurance information/requirements exchange	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
43	Provide specifications, including precision and accuracy of measurements	\$0.00	0.2 mons	Tue 2/2/10	Fri 2/5/10
44	Supply samples for fuel qualification tests	\$0.00	0.2 mons	Tue 2/2/10	Fri 2/5/10
45	Supply estimate of expected cost per plate of operations	\$0.00	0.2 mons	Tue 2/2/10	Fri 2/5/10
46	<b>Commercial fuel fabricator (currently B&amp;W Lynchburg)</b>	<b>\$0.00</b>	<b>6.7 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 4/6/10</b>
47	<b>Address issues resulting from Green Field Fabrication Facility proposal</b>	<b>\$0.00</b>	<b>0.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 10/6/09</b>
48	Maintaining fuel supply while transitioning from HEU to LEU	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
49	Documentation of contractual arrangement for linking plate production activity to full element assembly	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
50	Identification of contact for quality assurance information/requirements exchange	\$0.00	0.2 mons	Thu 10/1/09	Tue 10/6/09
51	Provide specifications, including precision and accuracy of measurements	\$0.00	0.2 mons	Thu 4/1/10	Tue 4/6/10
52	Supply samples for fuel qualification tests	\$0.00	0.2 mons	Thu 4/1/10	Tue 4/6/10
53	Supply estimate of expected cost per assembly of operations	\$0.00	0.2 mons	Thu 4/1/10	Tue 4/6/10

Table 2.2 Quality Assurance, Design, and Fresh Fuel Shipping Tasks

ID	Task Name	Cost	Duration	Start	Finish
54					
55	<b>Quality assurance approval/audit by HFIR staff for operations outside HFIR site</b>	<b>\$600,000.00</b>	<b>100.2 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 6/6/17</b>
56	<b>Interim fuel fabrication</b>	<b>\$250,000.00</b>	<b>24 mons</b>	<b>Thu 10/1/09</b>	<b>Wed 8/3/11</b>
57	Operations at Y-12	\$75,000.00	24 mons	Thu 10/1/09	Wed 8/3/11
58	Operations at Los Alamos	\$150,000.00	24 mons	Thu 10/1/09	Wed 8/3/11
59	Operations at Lynchburg	\$25,000.00	24 mons	Thu 10/1/09	Wed 8/3/11
60	<b>Fuel Fabrication Capability (site not yet determined)</b>	<b>\$350,000.00</b>	<b>86.1 mons</b>	<b>Mon 11/1/10</b>	<b>Tue 6/6/17</b>
61	Quality assurance for CD1 stage	\$75,000.00	12 mons	Mon 11/1/10	Fri 9/30/11
62	Quality assurance for CD2 stage	\$75,000.00	24 mons	Wed 11/30/11	Tue 10/1/13
63	Quality assurance for CD3 stage	\$150,000.00	36 mons	Wed 10/2/13	Tue 7/5/16
64	Approval of quality assurance plan for CD4 stage	\$50,000.00	12 mons	Wed 7/6/16	Tue 6/6/17
65					
66	<b>LEU fuel design studies</b>	<b>\$5,515,000.00</b>	<b>48.35 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 6/14/13</b>
67	HFIR/NNSA program coordination	\$1,200,000.00	36 mons	Mon 3/1/10	Fri 11/30/12
68	<b>Analyses</b>	<b>\$2,150,000.00</b>	<b>48.35 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 6/14/13</b>
69	<b>Studies for removing axial grading</b>	<b>\$1,300,000.00</b>	<b>24 mons</b>	<b>Thu 10/1/09</b>	<b>Wed 8/3/11</b>
70	Implementation of new thermal hydraulic analysis capability	\$800,000.00	24 mons	Thu 10/1/09	Wed 8/3/11
71	Neutronics studies to reduce/eliminate axial fuel grading	\$500,000.00	24 mons	Thu 10/1/09	Wed 8/3/11
72	<b>Flow test measurements at OSU</b>	<b>\$850,000.00</b>	<b>48.35 mons</b>	<b>Thu 10/1/09</b>	<b>Fri 6/14/13</b>
73	Advise/review structural analysis tests	\$150,000.00	36 mons	Thu 10/1/09	Wed 7/4/12
74	Design HFIR segments for OSU test loop	\$200,000.00	9 mons	Mon 1/4/10	Fri 9/10/10
75	Analyze data from structural analysis tests	\$500,000.00	36 mons	Mon 9/13/10	Fri 6/14/13
76	<b>Development of fuel specifications</b>	<b>\$2,165,000.00</b>	<b>36 mons</b>	<b>Thu 10/1/09</b>	<b>Wed 7/4/12</b>
77	HFIR staff fuel process review/comment	\$250,000.00	36 mons	Thu 10/1/09	Wed 7/4/12
78	Materials Science and Technology materials review/comment	\$375,000.00	36 mons	Thu 10/1/09	Wed 7/4/12
79	<b>Interim fuel fabrication</b>	<b>\$1,080,000.00</b>	<b>19.7 mons</b>	<b>Thu 10/1/09</b>	<b>Tue 4/5/11</b>
80	Develop test plan for measurements to support creation of a fuel specification for interim fuel	\$30,000.00	3 mons	Thu 10/1/09	Wed 12/23/09
81	Conduct measurements to support fuel specification	\$1,000,000.00	10 mons	Wed 4/7/10	Tue 1/11/11
82	Develop/approve fuel specification/drawings for HFIR LEU fuel plates	\$50,000.00	3 mons	Wed 1/12/11	Tue 4/5/11
83	<b>Commercial fuel fabrication</b>	<b>\$460,000.00</b>	<b>16 mons</b>	<b>Wed 4/6/11</b>	<b>Tue 6/26/12</b>
84	Develop second test plan for measurements to support creation of a fuel specification for commercial vendor	\$30,000.00	3 mons	Wed 4/6/11	Tue 6/28/11
85	Conduct second set of measurements to support fuel specification	\$400,000.00	10 mons	Wed 6/29/11	Tue 4/3/12
86	Develop/approve fuel specification/drawings for HFIR LEU fuel plates	\$30,000.00	3 mons	Wed 4/4/12	Tue 6/26/12
87					
88	<b>Fresh Fuel Shipping Cask (from fuel fabricator to HFIR)</b>	<b>\$10,000,000.00</b>	<b>86 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 5/4/17</b>
89	Specify fresh fuel characteristics, number of casks, regulations to be followed, approval agencies and approval paths with	\$120,000.00	4 mons	Fri 10/1/10	Thu 1/20/11
90	Issue Request for Proposals	\$90,000.00	3 mons	Fri 1/21/11	Thu 4/14/11
91	Review Proposals and Down-Select	\$90,000.00	3 mons	Fri 4/15/11	Thu 7/7/11
92	Selected Vendors Prepare Final Proposals	\$90,000.00	3 mons	Fri 7/8/11	Thu 9/29/11
93	Vendor Selection	\$30,000.00	1 mon	Fri 9/30/11	Thu 10/27/11
94	Develop Detailed Design of Cask	\$180,000.00	6 mons	Fri 10/28/11	Thu 4/12/12
95	Drop Testing of Prototype Cask	\$360,000.00	12 mons	Fri 4/13/12	Thu 3/14/13
96	Develop Safety Analysis Report for Cask	\$90,000.00	3 mons	Fri 3/15/13	Thu 6/6/13
97	Design Review by HFIR Operator	\$90,000.00	3 mons	Fri 6/7/13	Thu 8/29/13
98	Design Review by Approval Agencies	\$360,000.00	12 mons	Fri 8/30/13	Thu 7/31/14
99	Construct First Cask	\$5,314,000.00	12 mons	Fri 8/1/14	Thu 7/2/15
100	Testing and Certification of Cask	\$180,000.00	6 mons	Fri 7/3/15	Thu 12/17/15
101	Construct Additional Casks	\$2,820,000.00	12 mons	Fri 12/18/15	Thu 11/17/16
102	Testing and Certification of Additional Casks	\$180,000.00	6 mons	Fri 11/18/16	Thu 5/4/17
103	Shipment of first core to HFIR	\$6,000.00	0.2 mons	Mon 12/1/14	Thu 12/4/14
104					

Implementation of the LEU fuel cycle for this study was envisioned to be in two phases. The first phase would be to demonstrate acceptable reactor performance at an operating power level of 100 MW. The second phase would be the conversion to LEU fuel. The schedule shown in Table 2.3 includes these two phases.

End-of-cycle exposure for LEU elements will be greater than that for the current fuel elements. A variety of nuclear engineering analyses including radiation source term estimation, dose rate calculations, heat source estimation, and criticality safety calculations will have to be performed for the LEU fuel. All spent fuel operations – unloading of the reactor core, storage of spent fuel, transfer and loading of spent fuel to a shipping cask – will be re-evaluated using data from irradiations in ATR. The results of these studies will then be used to update the HFIR Safety Analysis Report.

## **2.7 OPERATIONS WITH SPENT FUEL OUTSIDE THE REACTOR**

Table 2.4 shows LEU fuel operations outside the reactor. Given that the LEU fuel elements have the same dimensions as the current HEU elements, there is a high probability that the current shipping cask (GE2000) can be used for spent LEU fuel. Nevertheless the cask must be licensed for a new fuel type (LEU) and for a greater discharge exposure than that for which it is currently licensed (2300 MWD).

The end point for that portion of the HFIR fuel cycle for which ORNL is responsible is the delivery of the spent fuel to Savannah River Site. Analysis and documentation costs related to the delivery and unloading of the fuel at SRS are assumed to be the responsibility of ORNL.

Table 2.3. Operations conducted inside the HFIR building

ID	Task Name	Cost	Duration	Start	Finish
105	<b>HFIR Reactor Building (7900)</b>	<b>\$45,400,000.00</b>	<b>135.8 mons</b>	<b>Fri 10/1/10</b>	<b>Fri 2/26/21</b>
106	<b>Fresh Fuel Operations outside of core</b>	<b>\$3,050,000.00</b>	<b>27 mons</b>	<b>Mon 10/1/12</b>	<b>Fri 10/24/14</b>
107	3 New Tools for handling operations inside reactor building + Spares	\$1,000,000.00	12 mons	Mon 10/1/12	Fri 8/30/13
108	Analysis of Other Tools	\$500,000.00	12 mons	Mon 10/1/12	Fri 8/30/13
109	Criticality Assessments	\$500,000.00	15 mons	Mon 10/1/12	Fri 11/22/13
110	Drop Calculations	\$1,000,000.00	12 mons	Mon 10/1/12	Fri 8/30/13
111	Second On-Site Transport Container from storage to reactor building (not required; will be removed at next schedule re	\$50,000.00	12 mons	Mon 11/25/13	Fri 10/24/14
112	<b>Reactor core-related operations</b>	<b>\$36,850,000.00</b>	<b>135.8 mons</b>	<b>Fri 10/1/10</b>	<b>Fri 2/26/21</b>
113	<b>Implementation step 1: Operation of Reactor at 100 MW</b>	<b>\$13,040,000.00</b>	<b>36 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 7/4/13</b>
114	<b>Address Nuclear, Mechanical, Thermal Characteristics for LEU Fuel at 100 MW</b>	<b>\$10,775,000.00</b>	<b>36 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 7/4/13</b>
115	Reactor Structural Analyses	\$5,075,000.00	36 mons	Fri 10/1/10	Thu 7/4/13
116	Seismic Analysis of Reactor Core Components and Vessel Support	\$2,500,000.00	36 mons	Fri 10/1/10	Thu 7/4/13
117	Structural/Seismic Analysis of core stack	\$2,500,000.00	36 mons	Fri 10/1/10	Thu 7/4/13
118	Revise Nuclear Criticality Safety Approval for LEU Fuel	\$75,000.00	6 mons	Fri 10/1/10	Thu 3/17/11
119	Accident Analysis	\$5,700,000.00	36 mons	Fri 10/1/10	Thu 7/4/13
120	Upgrade Analysis Methodology	\$1,200,000.00	24 mons	Fri 10/1/10	Thu 8/2/12
121	Accident Consequence Analyses	\$4,500,000.00	36 mons	Fri 10/1/10	Thu 7/4/13
122	Analyses for balance of plant operation at 100 MW	\$2,000,000.00	6 mons	Fri 10/1/10	Thu 3/17/11
123	Modify instrumentation	\$250,000.00	6 mons	Mon 10/3/11	Fri 3/16/12
124	Obtain regulatory approval	\$15,000.00	3 mons	Mon 3/19/12	Fri 6/8/12
125	Run cycle at 100 MW	\$0.00	1 mon	Mon 6/11/12	Fri 7/6/12
126	<b>Implementation step 2: Operation of Reactor with LEU fuel at 100 MW</b>	<b>\$23,810,000.00</b>	<b>119.5 mons</b>	<b>Mon 1/2/12</b>	<b>Fri 2/26/21</b>
127	Establish new reactor chemistry program for monitoring reactor coolant	\$300,000.00	4 mons	Mon 1/2/12	Fri 4/20/12
128	Obtain regulatory approval for loading fuel	\$10,000.00	3 mons	Mon 4/23/12	Fri 7/13/12
129	Core Performance Tests	\$19,500,000.00	49.1 mons	Tue 8/28/12	Wed 6/1/16
130	Reactor Control and Safety System Adjustment for New Fuel	\$1,500,000.00	12 mons	Fri 1/31/14	Thu 1/1/15
131	Startup Physics Tests (and cycle costs)	\$15,000,000.00	6 mons	Thu 12/17/15	Wed 6/1/16
132	Analyses for Physics/Thermal Hydraulic Tests	\$3,000,000.00	36 mons	Tue 8/28/12	Mon 6/1/15
133	Start first LEU fuel cycle with fuel from interim fabrication	\$0.00	1 mon	Thu 6/2/16	Wed 6/29/16
134	Receive first LEU fuel from FFC	\$0.00	1 mon	Mon 1/2/17	Fri 1/27/17
135	<b>PIE of LEU fuel</b>	<b>\$4,000,000.00</b>	<b>24 mons</b>	<b>Mon 4/29/19</b>	<b>Fri 2/26/21</b>
136	Clad exterior, corrosion, erosion	\$1,000,000.00	12 mons	Mon 4/29/19	Fri 3/27/20
137	Evaluation of fuel/diffusion barrier/clad interfaces	\$1,000,000.00	8 mons	Mon 4/29/19	Fri 12/6/19
138	Power profile via uranium depletion	\$1,000,000.00	12 mons	Mon 4/29/19	Fri 3/27/20
139	Disposal cost for assayed element	\$1,000,000.00	12 mons	Mon 3/30/20	Fri 2/26/21
140	<b>Spent fuel operations outside of core</b>	<b>\$5,500,000.00</b>	<b>24 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 8/2/12</b>
141	<b>Analyses Related to Discharged Fuel</b>	<b>\$1,000,000.00</b>	<b>12 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 9/1/11</b>
142	End of Cycle Source Terms, Decay Heat, Fission Products	\$500,000.00	9 mons	Fri 10/1/10	Thu 6/9/11
143	Consequence Analysis (Fission Product Transport)	\$500,000.00	12 mons	Fri 10/1/10	Thu 9/1/11
144	<b>Removal of Spent Fuel</b>	<b>\$400,000.00</b>	<b>12 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 9/1/11</b>
145	Drop Analysis	\$300,000.00	12 mons	Fri 10/1/10	Thu 9/1/11
146	Fuel Up-righting Methodology	\$50,000.00	3 mons	Fri 10/1/10	Thu 12/23/10
147	Hoist Issues	\$50,000.00	1 mon	Fri 10/1/10	Thu 10/28/10
148	<b>Spent Fuel Storage</b>	<b>\$2,300,000.00</b>	<b>12 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 9/1/11</b>
149	Structural Analysis: Shielding, Thermal, Criticality	\$2,000,000.00	12 mons	Fri 10/1/10	Thu 9/1/11
150	Requalification of Gamma Irradiation Facility	\$150,000.00	6 mons	Fri 10/1/10	Thu 3/17/11
151	Environmental Assessment	\$150,000.00	6 mons	Fri 10/1/10	Thu 3/17/11
152	<b>Documentation</b>	<b>\$1,500,000.00</b>	<b>24 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 8/2/12</b>
153	Upgraded approval	\$1,500,000.00	24 mons	Fri 10/1/10	Thu 8/2/12
154	<b>Sabotage Assessment</b>	<b>\$300,000.00</b>	<b>6 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 3/17/11</b>
155					

Table 2.4. Spent fuel operations outside reactor

ID	Task Name	Cost	Duration	Start	Finish
156	<b>Spent Fuel Shipping Cask</b>	<b>\$1,090,000.00</b>	<b>124 mons</b>	<b>Fri 10/1/10</b>	<b>Thu 4/2/20</b>
157	Irradiated Fuel Tools: Analysis and Design	\$300,000.00	6 mons	Fri 10/1/10	Thu 3/17/11
158	Relicensing of Cask and Analysis: Thermal, Structural, Shielding, Criticality (analyze and modify as needed)	\$750,000.00	12 mons	Fri 10/1/10	Thu 9/1/11
159	Ship first LEU core to Savannah River Site	\$40,000.00	0.2 mons	Mon 3/30/20	Thu 4/2/20
160					
161	<b>HFIR to Savannah River Site - Receipt of spent fuel</b>	<b>\$5,000,000.00</b>	<b>137.2 mons</b>	<b>Mon 10/26/09</b>	<b>Thu 4/30/20</b>
162	Record of Decision for DOE/EIS-0203	\$0.00	1 mon	Mon 10/26/09	Fri 11/20/09
163	3 New Tools for handling operations inside reactor building + Spares	\$200,000.00	12 mons	Mon 10/2/17	Fri 8/31/18
164	Analysis of Other Tools	\$500,000.00	12 mons	Mon 10/2/17	Fri 8/31/18
165	<b>Removal of Spent Fuel from cask</b>	<b>\$350,000.00</b>	<b>12 mons</b>	<b>Mon 10/2/17</b>	<b>Fri 8/31/18</b>
166	Drop Analysis	\$300,000.00	12 mons	Mon 10/2/17	Fri 8/31/18
167	Hoist Issues	\$50,000.00	1 mon	Mon 10/2/17	Fri 10/27/17
168	<b>Spent Fuel Storage</b>	<b>\$2,150,000.00</b>	<b>12 mons</b>	<b>Mon 10/2/17</b>	<b>Fri 8/31/18</b>
169	Structural Analysis: Shielding, Thermal, Criticality	\$2,000,000.00	12 mons	Mon 10/2/17	Fri 8/31/18
170	Environmental Assessment	\$150,000.00	6 mons	Mon 10/2/17	Fri 3/16/18
171	<b>Documentation</b>	<b>\$1,500,000.00</b>	<b>24 mons</b>	<b>Mon 10/2/17</b>	<b>Fri 8/2/19</b>
172	Upgraded approval	\$1,500,000.00	24 mons	Mon 10/2/17	Fri 8/2/19
173	<b>Sabotage Assessment</b>	<b>\$300,000.00</b>	<b>6 mons</b>	<b>Mon 10/2/17</b>	<b>Fri 3/16/18</b>
174	<b>Transfer of responsibility for fuel to SRS</b>	<b>\$0.00</b>	<b>1 mon</b>	<b>Fri 4/3/20</b>	<b>Thu 4/30/20</b>

### 3. SUMMARY AND CONCLUSIONS

Based on this preliminary plan, the total cost to ORNL expected to be funded by NNSA for conversion of the HFIR from HEU to LEU fuel through operation of the reactor with the first commercially fabricated core is \$76 million. A summary of costs by year based on the information presented in the previous section is shown in Table 3.1 and graphically presented in Fig. 3.1. A summary of costs by topic is provided in Table 3.2.

The purpose of this study was to respond to a request from the Department of Energy to prepare a schedule for the conversion of HFIR from HEU to LEU as input to an integrated multi-reactor conversion program plan. This HFIR plan is subject to revision based on feedback from the conversion program manager and other emerging developments. This HFIR plan was developed under the constraint that the conversion be completed by the end of fiscal year 2016. Upon completion of this task, one item has been identified as a potentially significant reduction to project cost - coordination with other U.S. reactor conversions to receive in-reactor measurement data and post-irradiation examination data thereby minimizing the number of tests needed to be performed at HFIR.

All policy decisions have significant technical and financial ramifications. Their consideration involves both the Department of Energy Office of Science and the National Nuclear Security Administration. Furthermore, two national laboratories (Oak Ridge and Los Alamos), the Y-12 National Security Complex, and any potential LEU fuel fabricators would be impacted by any changes to these policy decisions. Clearly such discussion is beyond the scope of the current study.


Table 3.1. HFIR LEU conversion cost by year

Fiscal Year	Cost (thousands of dollars)	
	Annual	Cumulative
2010	2,315	2,315
2011	14,689	17,004
2012	6,883	23,886
2013	7,284	31,170
2014	3,613	34,784
2015	10,233	45,017
2016	21,392	66,409
2017	616	67,025
2018	4,313	71,338
2019	2,306	73,644
2020	1,975	75,619
2021	446	76,065
<b>Grand Total</b>	<b>\$76,065</b>	

Table 3.2 HFIR LEU conversion cost by topic

ID	Task Name	Cost	Duration	Start	Finish
1	Conversion of HFIR from HEU to LEU (Pre-decisional)	\$76,065,000.00	148.85 mons	Thu 10/1/09	Fri 2/26/21
2					
3	Input required from organizations outside UT-Battelle/ORNL	\$8,460,000.00	89.2 mons	Thu 10/1/09	Tue 8/2/16
54					
55	Quality assurance approval/audit by HFIR staff for operations outside HFIR site	\$600,000.00	100.2 mons	Thu 10/1/09	Tue 6/6/17
65					
66	LEU fuel design studies	\$5,515,000.00	48.35 mons	Thu 10/1/09	Fri 6/14/13
87					
88	Fresh Fuel Shipping Cask (from fuel fabricator to HFIR)	\$10,000,000.00	86 mons	Fri 10/1/10	Thu 5/4/17
104					
105	HFIR Reactor Building (7900)	\$45,400,000.00	135.8 mons	Fri 10/1/10	Fri 2/26/21
155					
156	Spent Fuel Shipping Cask	\$1,090,000.00	124 mons	Fri 10/1/10	Thu 4/2/20
160					
161	HFIR to Savannah River Lab - Receipt of spent fuel	\$5,000,000.00	137.2 mons	Mon 10/26/09	Thu 4/30/20

Fig. 3.1 Conversion project expense







#### 4. REFERENCES

1. R. D. Cheverton and T. M. Sims, *HFIR Core Nuclear Design*, ORNL-4621, Oak Ridge National Laboratory (1971).
2. R.T. Primm III, R.J. Ellis, J.C. Gehin, D.L. Moses, J.L. Binder, and N. Xoubi, *Assumptions and criteria for performing a feasibility study of the conversion of the High Flux Isotope Reactor core to use low-enriched uranium fuel*, ORNL/TM-2005/269, Oak Ridge National Laboratory (2006).
3. R. T. Primm III, R. J. Ellis, J. C. Gehin, K. T. Clarno, K. A. Williams, and D. L. Moses, *Design Study for a Low-Enriched Uranium Core for the High Flux Isotope Reactor, Annual Report for FY 2006*, ORNL/TM-2006/136, November 2006.
4. R. T. Primm III, R. J. Ellis, J. C. Gehin, G. Ilas, J. H. Miller, and J. D. Sease, *Design Study for a Low-Enriched Uranium Core for the High Flux Isotope Reactor, Annual Report for FY 2007*, ORNL/TM-2007/45, November 2007.
5. R. T. Primm III, D. Chandler, G. Ilas, B. C. Jolly, J. H. Miller, and J. D. Sease, *Design Study for a Low-Enriched Uranium Core for the High Flux Isotope Reactor, Annual Report for FY 2008*, ORNL/TM-2009/87, March 2009.
6. United States Department of Energy, *Integration of Safety into the Design Process*, DOE Standard, DOE-STD-1189-2008, March 2008.
7. <http://www.em.doe.gov/Pages/spentfuel.aspx?compid=1> , December 2009.
8. J. D. Sease, R. T. Primm III, and J. H. Miller, *Conceptual Process for the Manufacture of Low-enriched Uranium/Molybdenum Fuel for the High Flux Isotope Reactor*, ORNL/TM-2007/39, September 2007.



**5. APPENDIX A  
RISKS AND OPPORTUNITIES**

<b>RISK GROUP</b>	<b>MAGNITUDE</b>	<b>PROBABILITY</b>
1. Incorrect or inadequate safety and performance analyses e.g., - accident analysis fails to demonstrate adequate safety margin at 100 MW - accident analysis identifies new issues - impacts of increased decay heat load relative to current cycle require major plant changes - modified reactor control parameters due to LEU/HEU neutronic differences - seismic/structural analyses fail to demonstrate adequate margin for reactor vessel - LEU changes lead to unacceptable results in HFIR PRA	High	High
2. Unacceptable increase in dose consequences due to changes in LEU spent fuel fission product inventory	Medium	Low
3. Analyses of LEU spent fuel operations require major plant changes e.g., - revised criticality analyses for storage and transportation - revised structural analyses for storage and transportation	Medium	Low
4. Difficulties in obtaining regulatory approvals (by others) e.g., - revised safety analyses - revised environmental impact documentation - revised transportation safety documentation - conduct and resolve issues from operational readiness reviews (not currently in HFIR project plan) - acceptance of spent fuel at SRS	High	High
5. Inadequate or unacceptable results from LEU fuel development and manufacturing efforts by others e.g., - acceptability of flow, irradiation, and post-irradiation testing - on-time availability of test results - ability to fabricate HFIR-spec fuel - quality of fuel from commercial vendor - on-time delivery of fuel from commercial vendor - cost of fuel from commercial vendor over remaining life of HFIR	High	Very high
6. Insufficient HFIR resources to support both ongoing operations and LEU conversion activities with projected staffing and budget due to overall impact of additional LEU work scope and increased cost of HEU fuel during transition	High	High
7. Significant contamination of HFIR systems and structures from LEU fuel failure impacts continued operations	High	Low

<b>OPPORTUNITY GROUP</b>	<b>MAGNITUDE</b>	<b>PROBABILITY</b>
1. New safety analysis tools improve current safety strategies e.g., reactor confinement	Medium	Low
2. New fuel handling tooling not needed	Low	Low

## INTERNAL DISTRIBUTION

- |  |  |
|--|--|
| 1. K. J. Beierschmitt ( <a href="mailto:beierschmitt@ornl.gov">beierschmitt@ornl.gov</a> ) | 8-10. R. T. Primm III ( <a href="mailto:primmrtdiii@ornl.gov">primmrtdiii@ornl.gov</a> ) |
| 2. S. E. Burnette ( <a href="mailto:burnettese@ornl.gov">burnettese@ornl.gov</a> )         | 11. R. R. Rawl ( <a href="mailto:rawlrr@ornl.gov">rawlrr@ornl.gov</a> )                  |
| 3. D. C. Christensen ( <a href="mailto:christensend@ornl.gov">christensend@ornl.gov</a> )  | 12. J. E. Rushton ( <a href="mailto:rushtonje@ornl.gov">rushtonje@ornl.gov</a> )         |
| 4. R. A. Crone ( <a href="mailto:cronera@ornl.gov">cronera@ornl.gov</a> )                  | 13. L. J. Satkowiak ( <a href="mailto:satkowiaklj@ornl.gov">satkowiaklj@ornl.gov</a> )   |
| 5. R. J. Ellis ( <a href="mailto:ellisrj@ornl.gov">ellisrj@ornl.gov</a> )                  | 14. J. D. Sease ( <a href="mailto:seasejd@ornl.gov">seasejd@ornl.gov</a> )               |
| 6. G. Ilas ( <a href="mailto:ilasg@ornl.gov">ilasg@ornl.gov</a> )                          | 15. K. A. Smith ( <a href="mailto:smithka@ornl.gov">smithka@ornl.gov</a> )               |
| 7. J. H. Miller ( <a href="mailto:millerjh2@ornl.gov">millerjh2@ornl.gov</a> )             | 16. ORNL Laboratory Records ( <a href="mailto:hamrindr@ornl.gov">hamrindr@ornl.gov</a> ) |

## EXTERNAL DISTRIBUTION

17. J. Matos, Argonne National Laboratory, 9700 S. Cass Avenue, Argonne, IL 60439 ([jim.matos@anl.gov](mailto:jim.matos@anl.gov))
18. D. M. Hewitt, Idaho National Laboratory, P.O. Box 1625, Idaho Falls, ID 83415-3750 ([Dana.Hewitt@inl.gov](mailto:Dana.Hewitt@inl.gov))
19. J. Roglans, Argonne National Laboratory, 9700 S. Cass Avenue, Argonne, IL 60439 ([roglans@anl.gov](mailto:roglans@anl.gov))
20. P. Staples, NA-212, U.S. Department of Energy, 1000 Independence Avenue SW, Washington, DC 20585 ([Parrish.Staples@nnsa.doe.gov](mailto:Parrish.Staples@nnsa.doe.gov))
21. John Stevens, Argonne National Laboratory, 9700 S. Cass Avenue, Argonne, IL 60439 ([johnstevens@anl.gov](mailto:johnstevens@anl.gov))
22. Daniel M. Wachs, MFC 791 B-147, Idaho National Laboratory, P.O. Box 6188, Idaho Falls, ID 83415 ([Daniel.Wachs@inl.gov](mailto:Daniel.Wachs@inl.gov))
23. Tracey Guida, University of Pittsburgh, Pittsburgh, PA, 15260 ([tlg29+@pitt.edu](mailto:tlg29+@pitt.edu))
24. Kathy Garcia, NA-212, U.S. Department of Energy, 1000 Independence Avenue SW, Washington, DC 20585 ([Kathy.Garcia@nnsa.doe.gov](mailto:Kathy.Garcia@nnsa.doe.gov))
25. Morris Hassler, Y-12 National Security Complex, ([hasslerme@y12.doe.gov](mailto:hasslerme@y12.doe.gov))
26. Eric C Woolstenhulme, P.O. Box 1625, Idaho Falls, ID 83415-3750 ([Eric.Woolstenhulme@inl.gov](mailto:Eric.Woolstenhulme@inl.gov))
27. Roger Klaffky, Office of Basic Energy Sciences, U.S. Department of Energy, 1000 Independence Avenue SW, Washington, DC 20585 ([roger.klaffky@science.doe.gov](mailto:roger.klaffky@science.doe.gov)).
28. Pedro Mantano, Office of Basic Energy Sciences, U.S. Department of Energy, 1000 Independence Avenue SW, Washington, DC 20585 ([pedro.montano@science.doe.gov](mailto:pedro.montano@science.doe.gov)).
30. Carol Sohn, of Basic Energy Sciences, U.S. Department of Energy ([carol.sohn@pns.science.doe.gov](mailto:carol.sohn@pns.science.doe.gov)).
31. Johnny O. Moore, U. S. Department of Energy, ([moorejo@ornl.gov](mailto:moorejo@ornl.gov))